

**Address:**

13345 NE Village Square Dr
C510
Woodinville WA 98072

Contact: Phone:

Email:
Electrical License #:

Justin Orellana

(425) 892-0913

info@jcs-constructionllc.com

JCSCOCS770NC

Scope Letter – Electrical Work

Project: Mountain View Middle School – Administrative Office Upgrades

Location: Sumner-Bonney Lake School District No. 320

Project ID: #E1560

Date: May 06, 2026

Prepared for: Sumner-Bonney Lake School District – General Contractor

All work is based on the contract documents (E0.1–E9.1, ED2.1–ED6.1), addenda, associated details, and our detailed takeoff.

Addenda Acknowledged: 1, 2

Base Bid – Lump Sum: \$ 109,865 (Excluding 10.0% Sales Tax)

Furnish and install all labor, materials, equipment, supervision, testing, and coordination required to complete the electrical scope for the Mountain View Middle School – Administrative Office Upgrades, including:

General Requirements

- Provide all labor, materials, equipment, and supervision necessary to complete the electrical scope for the Administrative Office Upgrades.
- Work includes mobilization, project management, temporary power, tool rentals, Parking, Dumpster Hauling, travelling, hotel accommodation, safety compliance, and final cleanup.
- All work will be performed under prevailing wage requirements and coordinated with school operations to minimize disruption. As-built documentation will be provided at project closeout.

Existing Conditions

Perform selective demolition of existing electrical systems throughout the administrative office areas.

- Work includes removal of Light fixtures, Switches, Data outlets, AV input plates, Auto-operator switches, Panic/call switches, Card readers, Wireless access points, Dis-connect switches, Door position switches, Electrified locksets, Horn/strobe devices, Intercom and clock units, Manual pull station, Power devices, Security push buttons, Wall-mounted security controls, Request-to-exit detectors, Security cameras.
- Reinstallation Work Includes Wireless access points, HD-Base TV outlets, Intercom units, IP cameras, Security push buttons, Card reader, Fire alarm devices
All demolition debris will be removed and disposed of in coordination with the GC.

Electrical Work

- Provide & Installation of new 30A/3P disconnect switch, 15A/3P breaker in existing panel
- Provide equipment connections for Air Handling Unit (AHU), Exhaust Fan (EF), Motorized door operator
- Provide & Installation of junction boxes and supporting hardware as required
- Provide & Installation of EMT and FLEX-S conduit systems with all fittings and supports
- Provide & Installation of copper conductors (#12, #10) for branch circuits
- Provide and install receptacles including Standard duplex, Dedicated, GFI, Motor-rated switch, Plug load controllers, Quadraplex (standard, controlled, AC, GFI combinations)
- Provide & Installation of conduit and wiring for lighting circuits
- Provide & Installation of new lighting fixtures including: 6" round downlights (Halo HC6), Round downlights (Portfolio LD2B), 2'x2' recessed troffers (Pinnacle LUCEN LIJ22), Under-cabinet strip fixtures (Halo HU30M)
- Provide & Installation of Lighting Controls, 1-way and 2-way switches Wall-mounted occupancy sensors, occupancy/vacancy sensors, and room controllers.

Communications (Division 27)

Provide backboxes and connections for:

- 1-port, 2-port, and 4-port telecom outlets
- Access control panels
- Ceiling-mounted telecom outlets
- Wireless access devices
- Intercom and clock units
- Provide conduit pathways with pull strings for future cabling

Electronic Safety & Security (Division 28)

Provide backboxes and install:

- Wall-mounted strobes
- Auto-operator security switches
- Panic/call switches
- Card readers
- Door position switches
- Electrified locksets
- Request-to-exit detectors
- Provide conduit pathways with pull strings for security cabling

Inclusions

- All labor, materials, equipment, and supervision required to complete the electrical scope
- All conduit, wire, fittings, supports, devices, and lighting fixtures
- All demolition and disposal related to electrical work
- Coordination with GC for shutdowns, inspections, and site logistics
- Prevailing wage, permitting fees, and as-built documentation
- Parking by owner

Exclusions

- Drywall repair, patching, painting, or structural modifications
- Correction of pre-existing code violations
- HVAC, plumbing, or mechanical work beyond electrical connections listed
- Utility transformer, meter upgrades, or utility company fees
- Low-voltage systems (communications, fire alarm, security)
- Temporary lighting, dumpsters, porta-potties, or material storage
- Overtime or shift work

Service Proposal Agreement

1. Scope of Work

The Contractor (JCS Electrical) agrees to furnish all labor and supervision necessary for the installation of the electrical system at the Property.

2. Change Orders

Any changes to the final approved Plans and Specifications, including but not limited to:

- Installation of additional electrical components not included above
- Delays
- Additional inspections/permits

Shall be considered a Change Order and must be mutually agreed upon in writing by both parties before the work is commenced. Change Orders will detail the scope of the change, the additional cost associated with the change, and any adjustments to the project schedule.

3. Warranties and Disclaimers

Contractor warrants that all electrical labor services will be performed in a professional and workmanlike manner, in accordance with applicable Washington State building codes and industry standards.

4. Insurance

Contractor will maintain its current General Liability and Workers' Compensation insurance policies, as required by Washington State law. A Certificate of Insurance (COI) is available upon request. Owner is responsible for obtaining any additional insurance coverage they deem necessary.

Any work not explicitly listed above or any deviations from the approved plans/specifications will be handled as a Change Order and must be mutually agreed upon in writing prior to commencement.

We look forward to working with you on this project. Please contact me directly with any questions or to discuss this scope further.